



SR #	CSI SECT	DESCRIPTION	QUANTITY	WASTAGE (10%)	QTY WITH WASTAGE	UNIT OF MEASUREMENT	UNIT COST	TOTAL ITEM COST	TOTAL TRADE COST
DIV.04 MASONRY									
EXTERIOR HOUSE SHELL									
1		Stone Headers	51	10%	56	LF			
2		4" Stone Window Sills	57	10%	63	LF			
3		Stone Wall Veneer	1977	10%	2175	SF			
4		Base of Wall Flashing	156	10%	172	LF			
5		Stone Cap at chimney over 10" wide	28	10%	31	SF			
6		Stone cap under 10" Wide	48	10%	53	LF			
7		Stone Chimney Veneer	220	10%	242	SF			
8		Angle iron Lintels at stone openings	51	10%	56	LF			
EXTERIOR SITE PAVING									
9		Brick Pavers at Driveway	2,214	10%	2435	SF			
10		Flagstone at back Patio	1,063	10%	1169	SF			
11		Flagstone at front Patio	185	10%	204	SF			
12		Flagstone at hot tub Patio	52	10%	57	SF			
13		Length of Risers	35	10%	39	LF			
14		Area of Treads	149	10%	164	SF			
15		Steeping Stone Pavers	12	0%	12	EA			
FIREPLACE VENEER									
16		Stone work at opening	56	10%	62	LF			
17		Stone work at fire places(4 Fire places)	240	10%	264	SF			
MASONRY WORK AT HOT-TUB									
18		Hot-tub veneer	87	10%	96	SF			
19		Hot-tub CMU	87	10%	96	SF			
20		Hot-tub Cap(2-1/2" Thick stone cap)	29	10%	32	LF			
MASONRY WORK FOR FIREPIT									
21		2-1/2" Thick Stone cap for Firepit	18	10%	20	LF			
22		Stone Veneer for Firepit	36	10%	40	SF			
SITE WALL VENEER									
23		Stone Veneer at site wall	572	10%	629	SF			
24		Stone cap at site wall veneer	88	10%	97	LF			
SUB TOTAL								\$ -	\$ -
OVERHEAD & PROFIT (25%)								25% \$ -	\$ -
TOTAL BID								\$ -	\$ -
PREPARED FOR :									
PREPARED BY :									

World Estimating

World Estimating